

CONTINUED FROM PRECEDING PAGE

CLEARANCE DELIVERY PHONE: For CD if una on freq ctc Tallahassee Apch at 850-942-8311. When Apch clsd, ctc Jacksonville ARTCC at 904-845-1592.

RADIO AIDS TO NAVIGATION: NOTAM FILE MAI.

MARIANNA (VL) (L) VORTACW 114.0 MAI Chan 87 N30°47.17' W85°07.47' 066° 27.5 NM to fld. 128/OE.

TACAN AZIMUTH unusable:

261°-276° byd 25 NM blo 3,000'

346°-061° byd 30 NM blo 2,000'

DME unusable:

261°-276° byd 25 NM blo 3,000'

346°-061° byd 30 NM blo 2,000'

VOR unusable:

050°-055° byd 61 NM

065°-068° byd 40 NM

075°-079° byd 42 NM

080°-100° byd 40 NM

110°-115° byd 40 NM

209°-347° byd 40 NM

261°-276° byd 25 NM blo 3,000'

316°-326° byd 20 NM blo 12,500'

346°-061° byd 30 NM blo 2,000'

WILLIS NDB (MHW) 359 LYZ N30°58.34' W84°31.50' 274° 5.8 NM to fld. 146/4W. NOTAM FILE MCN.

ILS 111.35 I-BGE Rwy 27. Class IE.

COMM/NAV/WEATHER REMARKS: All acft opr lclly at BGE must have a two-way radio capable of transmitting/receiving on CTAF freq, one-stop tran acft are exempt from this requirement.

BALDWIN CO RGNL (See MILLEDGEVILLE on page 241)

BARROW CO (See WINDER on page 267)

BARWICK LAFAYETTE (See LAFAYETTE on page 235)

BAXLEY MUNI (BHC)(KBHC) 4 S UTC-5(-4DT) N31°42.83' W82°23.63'

201 B NOTAM FILE MCN

RWY 08-26: H5003X75 (ASPH) S-19 MIRL

RWY 08: PAPI(P2L)—GA 3.0° TCH 31'.

RWY 26: PAPI(P2L)—GA 3.0° TCH 31'.

SERVICE: **FUEL** 100LL, JET A+ **LGT** Dusk-dawn. MIRL Rwy 08-26 oper dusk-0300Z†; after 0300Z†—CTAF. Rotating beacon dusk-0300Z†. After 0300Z†, ACTVT rotg bcn—CTAF.

AIRPORT REMARKS: Attended Mon-Fri 1300-2100Z†. Fuel 24 hr credit card svc avbl.

AIRPORT MANAGER: (912) 367-3232

WEATHER DATA SOURCES: AWOS-3PT 118.2 (912) 705-5865.

COMMUNICATIONS: CTAF/UNICOM 122.8

® **JACKSONVILLE CENTER APP/DEP CON** 127.575

CLEARANCE DELIVERY PHONE: For CD ctc Jacksonville ARTCC at 904-845-1592.

RADIO AIDS TO NAVIGATION: NOTAM FILE AMG.

ALMA (H) TACAN Chan 98 AMG (115.1) N31°32.19'

W82°30.49' 029° 12.1 NM to fld. 194/OE. tac unmonitored

0300-1100Z†.

TACAN AZ unusable:

Blw 3,000'


TACAN DME unusable:

Blw 3,000'

JACKSONVILLE

H-9B, 12F, L-24H

IAP



BERRIEN CO (See NASHVILLE on page 247)