

BARNWELL RGNL (BNL)(KBNL) 1 NW UTC-5(-4DT) N33°15.46' W81°23.29'

246 B NOTAM FILE AND

CHARLOTTE
H-9B, 12G, L-24I

RWY 17-35: H5119X100 (ASPH) S-69, D-99 PCN 26/F/B/X/T MIRL

RWY 17: ODALS. PAPI(P2L)—GA 3.04° TCH 55'. Tree. Rgt ttc.

RWY 35: PAPI(P2L)—GA 3.0° TCH 45'. Tree.

RWY 05-23: H4526X70 (ASPH-AFSC) S-12

RWY 23: Rgt ttc.

SERVICE: FUEL 100LL, JET A, MOGAS LGT ACTVT ODALS Rwy 17;
MIRL Rwy 17-35—CTAF. PAPI Rwy 17 and Rwy 35 oper consly, otr
times—CTAF.

AIRPORT REMARKS: Attended 1400-2200Z. 100LL fuel 24 hr credit card
svc avbl. Emerg fuel shutoff lctd on right side of trml bldg atchd to elec
vault. Rwy 05-23 has multiple cracks and raveling producing FOD.
Rwy thrs not mkd. Rwy 05-23 rstd use to acft weighing 12,500 lbs
and less. Aerobic act west of Rwy 17-35. When active, incoming
acft apch arpt from east.

AIRPORT MANAGER: 803-300-1190

WEATHER DATA SOURCES: AWOS-3PT 119.775 (803) 259-4536.

COMMUNICATIONS: CTAF/UNICOM 122.8

® **JACKSONVILLE CENTER APP/DEP CON** 132.925

GCO 121.725 (ZJX CLEARANCE DELIVERY)

CLEARANCE DELIVERY PHONE: For CD if una via GCO ctc Jacksonville ARTCC at 904-845-1592.

RADIO AIDS TO NAVIGATION: NOTAM FILE CAE.

COLUMBIA (VH) (H) VORTACW 114.7 CAE Chan 94 N33°51.44' W81°03.23' 207° 39.6 NM to fld. 404/2W.

VOR unusable:

000°-073° byd 35 NM blo 6,000'

200°-234° byd 12 NM blo 3,000'

235°-245° byd 12 NM blo 6,000'

246°-289° byd 12 NM blo 3,000'

290°-305° byd 12 NM blo 2,400'

306°-344° byd 30 NM

345°-359° byd 10 NM blo 5,000'

