

SEDONA (SEZ)(KSEZ) 2 SW UTC-7 N34°50.92' W111°47.31'
 4831 B TPA—See Remarks NOTAM FILE SEZ
RWY 03-21: H5132X100 (ASPH) S-15, D-30 MIRL 1.8% up NE
RWY 03: REIL. PAPI(P4L)—GA 3.0° TCH 44'.

PHOENIX
H-4J, L-8G
IAP

RWY 21: REIL. PAPI(P4L)—GA 3.5° TCH 49'. Fence.
SERVICE: S2 **FUEL** 100LL, JET A **LGT** ACTVT REIL Rwy 03 and Rwy 21; PAPI Rwy 03 and Rwy 21; MIRL Rwy 03-21—CTAF. Rwy 21 PAPI unusbl byd 2.0 NM.

NOISE: Noise abatement proc in efct; scenic fit blw 6500 ft MSL NA.

AIRPORT REMARKS: Attended May-Sep 1400-0100Z, Oct-Apr 1400-0300Z. Arpt on 500 ft Mesa, Windshear, turb, up and down drafts near Mesa edge. Fuel A 10 pct SHF (Synthetic Hydrocarbon Fuels). Aft hr call out fee. Birds and wildlife on and invof arpt. TPA—prop 6004(1173) Jet 7004(2173). Rwy 03 calm wind rwy for Indg; Rwy 21 for tkof. Overnight tnst fee.

AIRPORT MANAGER: 928-282-4487

WEATHER DATA SOURCES: AWOS-3PT 118.525 (928) 282-1993.

COMMUNICATIONS: CTAF/UNICOM 123.0

COTTONWOOD RCO 122.3 (PRESCOTT RADIO)

® **PHOENIX APP/DEP CON** 126.375

CLEARANCE DELIVERY PHONE: For CD etc Phoenix Apch at 602-306-2565.

RADIO AIDS TO NAVIGATION: NOTAM FILE FLG.

FLAGSTAFF (VH) (DH) VOR/DME 113.85 FLG Chan 85(Y)

N35°08.83' W111°40.45' 184° 18.8 NM to fld. 7026/14E.

VOR unusable:

- 030°-040° byd 40 NM
- 041°-051° byd 40 NM blo 18,000'
- 052°-061° byd 40 NM
- 062°-072° byd 40 NM blo 18,000'
- 073°-140° byd 40 NM
- 141°-151° byd 40 NM blo 18,000'
- 152°-159° byd 40 NM
- 160°-177° byd 40 NM blo 11,000'
- 160°-177° byd 48 NM blo 12,000'
- 160°-177° byd 63 NM
- 178°-231° byd 40 NM
- 232°-252° byd 40 NM blo 18,000'
- 253°-295° byd 40 NM
- 335°-030° byd 19 NM blo 24,000'
- 350°-026° byd 40 NM

DME unusable:

- 230°-255° byd 20 NM blo 15,000'

HELIPAD H1: H50X50 (CONC)

HELIPORT REMARKS: Rwy H1 flood lgts. HOP fm heli S and W of rwy; HOP rstrd to heli adj to twy intxn A7 SW main trml bldg.

